



NXOS upgrade failure with error : "Return code 0x40930011 (Digital signature verification failed)"



https://kb.netapp.com/Advice_and_Troubleshooting/Data_Storage_Systems/Fabric%2C_Interconnect_...

Updated: Tue, 10 Aug 2021 01:34:55 GMT

Applies to

- Cisco Nexus Switches
- NXOS releases prior to 9.2(2)

Issue

- Upgrading NXOS from a version prior to 9.2(2) fails with the below error code

```
Verifying image bootflash:/nxos.9.2.2.bin for boot variable  
"nxos".[##### ] 90% -- FAIL.
```

Return code 0x40450030 (Digital signature verification failed).
Pre-upgrade check failed. Return code 0x40930011 (Image verification failed).

- Upgrade will be aborted without completion